



New Enterprise Stone & Lime Co., Inc.

## Project Spotlight

### MasterFiber<sup>®</sup> MAC 360FF

#### Macrosynthetic Fiber

### Plank Road Drive Thru & Dumpster Pad

#### **Location**

Altoona, PA

#### **Contractor**

Lawruk Builders, Inc.

#### **Concrete Producer**

New Enterprise Stone & Lime Co., Inc.

#### **Concrete Volume**

70 cubic yards

#### **Fiber Dosage**

Drive Thru - 3 lbs./cubic yd

Dumpster Pad - 6 lbs./cubic yd

#### **Application**

Exterior Pavement

To speed construction, the contractor submitted 360FF at 3 lbs./yd<sup>3</sup> to replace the 6x6 - 6 gauge mesh in the drive thru and 6 lbs./yd<sup>3</sup> to replace the two mats of #3 bar @ 18" o.c.e.w. in the dumpster pad.



**Altoona Sales Area - Adrian "Ace" Snyder – 814.330.2425**

**Harrisburg & Chambersburg Sales Area – Scott Eichelberger – 717.729.1816**

**Lancaster Sales Area – Darryl Keiser – 717.286.5894**

**Allentown Sales Area – Clint Renninger – 484.256.8343**