



**New Enterprise Stone & Lime Co., Inc.**

## **Project Spotlight**

**MasterFiber<sup>®</sup> MAC 360FF**

**Macrosynthetic Fiber**

### **Cardiology Associates of Altoona**

***Location***

Roaring Spring, PA

***Contractor***

Leonard S. Fiore, Inc.

***Concrete Producer***

New Enterprise Stone & Lime Co., Inc.

***Concrete Volume***

45 cy - composite metal deck

117 cy - slab on ground

***Fiber Dosage***

4 lbs./cubic yd - composite metal deck

3 lbs./cubic yd - slab on ground

***Application***

Composite metal deck

Slab on ground



**Cardiology Associates  
of Altoona, L.L.P**

Contractor replaced 6x6-8 gauge mesh in the slab-on-ground with 3 lbs./cy of MasterFiber MAC 360FF. The Steel Deck Institute required a minimum of 4 lbs./cy of MasterFiber MAC 360FF to replace the 6x6-10 gauge mesh in the composite metal deck.

***Altoona Sales Area - Adrian "Ace" Snyder - 814.330.2425***

***Harrisburg & Chambersburg Sales Area - Scott Eichelberger - 717.729.1816***

***Lancaster Sales Area - Darryl Keiser - 717.286.5894***

***Allentown Sales Area - Clint Renninger - 484.256.8343***